

JCB 4CX PLUS

4CX 14 FIX DIPPER, 74KW (100HP) T2 ENGINE, MANUAL ENGINE:

JCB DIESELMAX 4.4L, 4 CYLINDER, 74.2KW (100HP), 95A

MANUAL CONTROLS

TURBO INTERCOOLED

MAINFRAME: 7'8" AWS SIDESHIFT

PUMP: 144 LPM (32 GPM) TRIPLE GEAR PUMP

EXCAVATOR: 14' FIXED DIPPER

HEAVY LIFT

200AN08 - 4CX

MICHELIN XMCL 440/80-28 POWERSHIFT TRANS, AWS

CAB WITH HEATER & AIR CONDITIONING

CLOTH SUSPENSION SEAT

CAB ELECTRICS, LIVELINK, HEATED SCREEN

HAMMER PIPEWORK, END BOOM DAMP

3/8 LOADER PIPEWORK, SRS

ENGLISH TERRITORY PACK EXPORT

DIRECT MOUNT 6 IN 1 WITH FORKS, 2350MM (92") FOR USE ON

2WS/AWS STANDARD DUTY WITH FORKS

400MM (16") HEAVY DUTY PROFILE

0.09M3 (0.12YD3) SAE HEAPED CAPACITY

ROTATING BEACON

REVERSE ALARM

FRONT LAMPS (RH DIP)

EXTERIOR MIRRORS

INTERIOR MIRROR

8 LED WORKLIGHTS, 4 FRONT & 4 REAR (YELLOW ROOF)

EXCAVATOR CONTROL PATTERN ISO +